



LIST OF EQUIPMENT SCHEDULE											
ITEM	SYMBOL	DESCRIPTION	LOCATION	SYSTEM COMPONENT & SPECIFICATION	CAPACITY	Q' TY	ELECTRICAL DATA			CONTROL FUNCTION	REMARK
							KW	RPM	V/φ/HZ		
1	CWP-1,2	COLD WATER PUMP	PUMP ROOM GROUND FL.	VERTICAL MULTISTAGE CENTRIFUGAL PUMP	Q = 10 CU.m./hr. TDH = 35 m.	2	1.5	2900	380/3/50	LEVEL SWITCH CONTROL UNDER GROUND TANK. - LOW LEVEL ALARM + BUZZER & CWP-1,2 CUT OFF - HIGH LEVEL ALARM + BUZZER 2 ROOF FL. - HIGH-HIGH LEVEL ALARM + BUZZER - HIGH LEVEL (CWP-1,2 STOP) - LOW LEVEL STAGE (ONE PUMP START) - LOW LEVEL STAGE (TWO PUMP START) - LOW-LOW LEVEL 2 ALARM + BUZZER & PBS CUT OFF	ONE PUMP OPERATING (ONE DUTY, ONE STANBY)
2	PBS	PACKAGE BOOSTER PUMP	DECK FLOOR PLAN	END-SUCTION PUMP CONSTANT PRESSURE BOOSTER SET WITH DIAPHRAGM TANK FULLY ASSEMBLY TESTED, COMPLETE WITH CONTROL DEVICE, PUMP BASE, SPRING ISOLATOR AND ACCESSORY	Q = 2x15 CU.m./hr. TDH = 25 m.	1	2x2.0	2900	380/3/50	AUTO MATIC OPERATED WITH PRESSURE SWITCH	VOLUME OF PRESSURE TANK 300 LITERS.

02 SN 22	กรมสรรพสามิต ส่วนมาตรฐานการออกแบบ กลุ่มพัฒนาและตรวจสอบทางเทคนิค	แบบแสดง โดอะแกรมแนวตั้งระบบจ่ายน้ำประปา โดอะแกรมแนวตั้งระบบป้องกันอัคคีภัย	แบบแสดง 60-001-1793 มาตรฐาน กุมภาพันธุ์ 2560	เขียนแบบ นายชัยณรงค์ พงศ์ศรี เขียนแบบ นางสาวปิยะมาศ ลิ้มปิติภักษ์พงศ์ เขียนแบบ นายธวัชชัย หวังมวนกลาง เขียนแบบ นายพิศาล สิงห์พันธ์	วิศวกร นายชัยยศ พิณจิตรสมุทร สย. 6856 วิศวกร นายสุเวษ พงษาพันธ์ ภัย. 12509 วิศวกรโยธาชำนาญการ วิศวกรโยธาชำนาญการ ตรวจสอบ ผู้อำนวยการส่วนมาตรฐานการออกแบบ เห็นชอบ (แทน) ผู้อำนวยการกลุ่มพัฒนาและตรวจสอบทางเทคนิค
	โครงการก่อสร้างอาคารชุดพักอาศัย 5 ชั้น				